

# CENTRAL STATE HOSPITAL – Milledgeville, Georgia

## KITCHEN FACILITY GREASE TRAP ASSESSMENT

**SCOPE** Addition of two new grease interceptors to accommodate large volumes of kitchen discharge flow from the existing kitchen facility.



**Owner**  
GA Dept. of Human Resources

**Mechanical Contractor**  
Green & Associates

**Prime Consultant**  
Johnson, Spellman &  
Associates

**Construction Cost**  
\$50,000 (est.)

### SPECIAL CIRCUMSTANCES

- Verify existing site conditions including existing waste piping and grease trap layout.
- Perform dye testing of existing waste system.
- Assess which existing fixtures are piped through the existing grease trap.
- Modification of existing grease trap piping.
- Addition of two 1,500-gallon grease traps in series downstream of existing modified grease trap.
- Provision for two additional grease traps.
- Coordination of new grease waste line with existing site utilities.
- Addition of new sanitary sewer manhole in existing drive.
- Reconfiguration of existing waste piping into grease traps.

